

DECISION REPORT · INDIA

See the economics before the machinery.

Build a transparent AAC block project model from your local prices, capacity and investment assumptions.

LIVE OPERATING MARGIN

₹698 /m³

At 80% plant utilisation · ₹8.37 per piece

01 Project

02 Production cost

03 Investment

04 5-year DPR

01 · PROJECT BASIS

Define the plant you intend to build.

Rated plant capacity 500 m³/day 0 to 2,000 m³/day - adjusts in steps of 10 4 inch (100 mm) ▾ 41,665 pieces/day 83.33 blocks in 1 m³	Main silica material Sand ▾	Operating days 28 days/month	Selling Price 3000 ₹/m³ 4 inch (100 mm) ▾ Price per piece 36 Automatically equals ₹3,000/m³
Expected plant utilisation 11,200 m³ estimated monthly production 80%			

Connected load	Boiler guidance	Steam consumption	Monthly output
600 HP	6 TPH	140 kg/m³	11,200 m³

02 · PRODUCTION ECONOMICS

ESTIMATED PRODUCTION COST

₹2,302 /m³

₹27.63 per piece

Raw material recipe

Quantity and price are editable

MATERIAL	CONSUMPTION KG/M ³	PRICE ₹/KG	COST/M ³
Sand	450	0.5	₹225

Cement	105	5.5	₹578
Lime	60	8	₹480
Aluminium	0.4	450	₹180
Gypsum	10	4	₹40
Mould oil	0.7	30	₹21
Soap oil	0.3	25	₹8

Boiler fuel Coal	Fuel price 7 ₹/kg	Automatic steam consumption 140 kg/m³ 140 kg base for 6 TPH boiler	
		Efficient Steam Transfer Capacity-based steam saving	
Steam generation 4 kg steam/kg fuel Editable base boiler efficiency	Efficient Heat Utilization Increases steam generation by 15% for this boiler capacity		
EFFECTIVE STEAM GENERATION 4.00 kg/kg fuel	FUEL CONSUMPTION 35.00 kg fuel/m³	Power consumption 15 kWh/m³	
Efficient Control Panel System Reduces power consumption by 15% - effective 15.00 kWh/m³		Electricity tariff 8 ₹/kWh	Other process cost 80 ₹/m³
Process wastage 4 %			

MONTHLY MANPOWER COST
₹18,73,000
87 shift positions - ₹167/m³

RUNNING SHIFTS
2 shifts
Updates production & stock-yard manpower

View / edit manpower calculation

Segregation cost 35 ₹/m³	Loading cost 45 ₹/m³
Auto Palletize System Selected: segregation cost becomes zero	With Pallet Loading or Palletless Stacking Selected: loading cost becomes zero
Transportation cost 0 ₹/m³	Unloading cost 0 ₹/m³

Raw material ₹1,531	Steam ₹245	Power ₹120	Other + waste ₹159	Payroll ₹167
Segregation ₹35	Loading ₹45	Transportation ₹0	Unloading ₹0	

Use quotation-backed values.

No machinery price or investment figure is automatically assumed by Laxmi En-Fab.

Commercial safeguard Enter actual values available to you. The complete investment proposal will be provided separately after technical discussion and submission.

Plant & machinery 0₹ Entered value: ₹0	Utilities 0₹ Entered value: ₹0 Boller, steam, water, air & distribution	Electrical 0₹ Entered value: ₹0 Load, transformer, panels & cabling	Civil & structures 0₹ Entered value: ₹0 Buildings, foundations, storage & lab
Execution 0₹ Entered value: ₹0 Erection, cranes, testing & training	Pre-operative expense 0₹ Entered value: ₹0 Approvals, recruitment, insurance & fees	Contingency 0₹ Entered value: ₹0	Interest during construction 0₹ Entered value: ₹0

ESTIMATED WORKING CAPITAL ₹4,14,00,000 45 operating days · rounded to nearest ₹1 lakh	Receivable period 30days	Raw-material stock 7days	Finished-goods stock 7days
--	--	--	--

Financial calculation parameters

Editable DPR calculation inputs

These assumptions directly recalculate depreciation, outstanding-loan interest, cash accrual and DSCR for all five years.

Promoter equity 30%	Loan interest 12% p.a.	Loan repayment 7years	Depreciation 8% p.a.	Income tax 25%	Net GST funding impact 0₹
Year 1 utilisation 60%	Year 2 utilisation 75%	Year 3 utilisation 85%	Year 4 utilisation 90%	Year 5 utilisation 90%	

04 · FIVE-YEAR DPR

From operating margin to debt service.

TOTAL PROJECT OUTLAY
₹4,14,00,000
Including estimated working capital

Monthly EBITDA ₹78,14,552 at selected utilisation	Break-even utilisation 17.9% 2,500 m³/month	Operating margin 23.3% ₹698 per m³	Project payback Within Year 1 cash-accrual basis
--	--	---	---

PROJECTION	YEAR 1 60% UTILISATION	YEAR 2 75% UTILISATION	YEAR 3 85% UTILISATION	YEAR 4 90% UTILISATION	YEAR 5 90% UTILISATION
Production (m³)	1,00,800	1,26,000	1,42,800	1,51,200	1,51,200
Revenue	₹30,24,00,000	₹37,80,00,000	₹42,84,00,000	₹45,36,00,000	₹45,36,00,000
EBITDA	₹7,03,30,968	₹8,79,13,710	₹9,96,35,538	₹10,54,96,452	₹10,54,96,452
Depreciation	₹0	₹0	₹0	₹0	₹0
Interest	₹34,77,600	₹29,80,800	₹24,84,000	₹19,87,200	₹14,90,400
Profit before tax	₹6,68,53,368	₹8,49,32,910	₹9,71,51,538	₹10,35,09,252	₹10,40,06,052
Cash accrual	₹5,01,40,026	₹6,36,99,683	₹7,28,63,654	₹7,76,31,939	₹7,80,04,539
DSCR	7.04×	9.36×	11.37×	12.99×	14.12×

AUTOMATIC WORKABLE CAPACITY SUGGESTION

Complete investment inputs to receive a capacity suggestion

The recommendation requires project investment, finance assumptions and operating costs.

DECISION DOCUMENT

Download the complete branded DPR.

Includes assumptions, cost details, manpower schedule, investment and five-year projections.

Unlock DPR report ↗